



कालिका गाउँपालिका गाउँ कार्यपालिकाको कार्यालय



प.सं. २०८२/०८३

च.नं. :

धैबुङ्ग, रसुवा
बागमती प्रदेश
कालिका गाउँपालिका
गाउँ कार्यपालिका
धैबुङ्ग, रसुवा
बागमती २०७३

फोन: ०१०-५४२०९८


विषय : सोलार बत्ती उपलब्ध गराउने सम्बन्धी सूचना ।

(प्रथम पटक प्रकाशित मिति: २०८३/०१/२२)

कालिका गाउँपालिका रसुवाको आ.व. २०८२/०८३ को गाउँपालिका तर्फको स्वीकृत वार्षिक कार्यक्रम अनुसार गाउँपालिकाको कार्यालयलाई आवश्यक पर्ने सोलार बत्ती जडान तथा व्यवस्थापन गर्न इच्छुक फर्म वा व्यवसायीहरूले यो सूचना प्रकाशित मितिले ७ (सात) दिन भित्र कालिका गाउँपालिकाको कार्यालयमा यसै सूचना साथ संलग्न गरिएको BOQ मा हस्तलिखित विवरण भरी आवश्यक कागजात सहित सूचीकृत भई के-कति दररेटमा उपर्युक्त अनुसारको सोलार बत्ती जडान तथा व्यवस्थापन गराउन सकिन्छ, सो सम्बन्धमा सिलबन्दी प्रस्ताव समेत पेश गर्नुहुन जानकारी गराइन्छ ।

तपसिल :

१. सक्कल निवेदनको साथमा BOQ सहितको दररेट,
२. फर्म वा व्यवसाय दर्ता,
३. प्यान/भ्याट दर्ता
४. आ.व. २०८१/०८२ को कर चुक्ता ।


.....
धर्मराज न्यौपाने
प्रमुख प्रशासकीय अधिकृत
प्रमुख प्रशासकीय अधिकृत

Kalika Rural Municipality
Office of Rural Municipal Executive
Dhaibung, Rasuwa
Bagmati Province, Nepal
Bill of Quantity (BOQ)



प्रमुख प्रशासकीय अधिकृत

Name of Project : SOLAR STREET LIGHT INSTALLATION
Location : Kalika 1&2

Pay Item No.	DESCRIPTION	Unit	Quantity	Rate		Remarks
				In Figures	In Words	
	Procurement Works					
	Supply, installation & commissioning of Solar PV panel (200wp) as per technical					
1.0	Specification Supply, installation & Fitting of lithium ion battery (12 V), .80 AH@c10, Solar Street Light Battery.	Nos	7.00		s	
2.0	Supply, installation & commissioning of solar charge controller with dusk to dawn function, three stage dimming function (20a/12) as per technical specification.	Nos	7.00			
3.0	Supply, installation & commissioning of Solar Lamp (KED), 40 Watt as per Technical Specification mentioned on document	Nos	7.00			
4.0	Supply, installation & connection of 8m long hot galvanized pole with diameter of pole section 5" for bottom 4.5m, 4" for middle 1.75m and 3" for top 1.75m as per technical specification	Nos	7.00			
5.0	Supply, installation & commissioning of interconnecting Wires & other Accessories (Nut- Bolt, Earthing) as per Technical Specification.	LS	7.00			
6.0	Perform all civil works along with light pole on specified location selection by buyer and excavation of 1500*300 mm round / square deep hole and concrete foundation. The structure should be facing sun direction tilted at 30 degree. Pole and mounting structure must be designed accordingly.	LS	7.00			
				Total Without VAT =		
				VAT (13%) =		
				Grand Total =		

F/N: 2082/83

Name of Contractor :

Date:

Signature: